# <u>CITY OF VISALIA</u> HISTORIC PRESERVATION ADVISORY COMMITTEE Wednesday, January 11, 2023, at 5:30PM

CHAIR: Walter Deissler VICE-CHAIR: Tyler Davis

COMMITTEE MEMBERS: Patty Kane, Michael Kreps, Jay Hohlbauch, Jordan Mulrooney

# City of Visalia Community Development Building 315 East Acequia Avenue, Visalia CA

# <u>AGENDA</u>

#### A. Citizen's Comments

#### B. Meeting Minutes

1. December 14, 2022, Regular Meeting

#### C. Project Reviews:

 HPAC No. 2022-26 (Continued Hearing): A request by Walter Deissler for a Conditional Use Permit to convert an existing single-family residence into a bed and breakfast inn and conduct exterior alterations to an existing guest house, within the R-1-5 (Single Family Residential, 5,000 square foot minimum site area) Zone. The project site is located at 513 North Encina Street (APN: 094-353-011).

#### D. Discussion Items

- 1. January 17, 2023, Visalia City Council Meeting Consideration of Karen Ayala Nomination to the HPAC.
- 2. 2023 HPAC Schedule of Meetings
- 3. Tulare County Association of Realtors Luncheon February 16, 2023
- 4. Committee and Staff Comments
  - a. Project Updates
- 5. Identification of Items for Future Agendas

#### E. Adjournment

In compliance with the Americans Disabilities Act, if you need special assistance to participate in meetings call (559) 713-4443 (Staff Representative) 48-hours in advance of the meeting. For Hearing Impaired – Call (559) 713-4900 (TTY) 48-hours in advance of the scheduled meeting time to request signing services. Visually Impaired - If enlarged print or a Braille copy is desired, please request in advance of the meeting and services will be provided as possible after the meeting. City Staff to the Committee is Cristobal Carrillo, Associate Planner, 559-713-4443, <u>cristobal.carrillo@visalia.city</u>.

Éste Aviso es para informarle que habra una audiencia para el público ante el Comité de Preservación Histórica de la Ciudad de Visalia. Para más información, o para dar comentario público respecto a esta solicitud, por favor llame Cristobal Carrillo, Associate Planner, al numero (559) 713-4443 o <u>cristobal.carrillo@visalia.city</u>.

Additional information about the Historic Preservation Advisory Committee may be found by contacting Cristobal Carrillo, Associate Planner at 559-713-4443, or emailing <u>cristobal.carrillo@visalia.city</u>.



# CITY OF VISALIA HISTORIC PRESERVATION ADVISORY COMMITTEE Wednesday, December 14, 2022, at 5:30PM

CHAIR: Walter Deissler VICE-CHAIR: Tyler Davis

Hohlbauch absent. All other members present.

COMMITTEE MEMBERS: Patty Kane, Michael Kreps, Jay Hohlbauch, Jordan Mulrooney

MEMBERS OF THE PUBLIC: Bruce Buyuklian, Karen Ayala, Janelle Hickey

CITY STAFF: Cristobal Carrillo, Associate Planner

# City of Visalia Administration Building 220 N. Santa Fe Street, Visalia CA

# <u>AGENDA</u>

#### A. Citizen's Comments

#### None.

- B. Meeting Minutes
  - 1. November 9, 2022, Regular Meeting

A motion was made by Kreps, seconded by Kane, to approve the meeting minutes for November 9, 2022. The motion was approved 5-0 (Hohlbauch absent).

#### C. Project Reviews:

 HPAC No. 2022-25: A request by Bruce Buyuklian for an addition to an office on a site within the O-C (Office Conversion) Zone. The project site is located at 1304 W. Center Street (APN: 093-264-019).

Staff presented its report and recommended that HPAC approve the exterior alterations as modified and conditioned by staff. Public comment in favor of the proposal was received from contractor Bruce Buyuklian. Buyuklian clarified that additional windows had already been provided to the addition, as shown on the Floor Plan, and expressed concern with requiring the roof pitch of the addition to match that of the existing porch. Kreps stated that he would prefer that the new windows within the addition be wooden, and that there should be a more pronounced vent feature at the eastern end of the addition. Deissler also stated a preference for wood windows, adding that he would rather see that the roof slope of the addition be more in line with the existing structure. Deissler also asked if it would be possible to keep the chimney. Buyuklian stated that the chimney should be removed since it was not visible from the sidewalk and served no purpose. He added that it would also be in the way of the roof for the addition. Following discussion, a motion was made by Kreps to approve the proposal, with modifications as follows:

- That the height of the addition matches the height of the existing structure;
- That the chimney be allowed to be removed;
- That wood windows be required for the addition; and
- That conditions of approval be altered to support the modifications made by the Committee (Removal of Condition No. 3, and alterations to Condition Nos. 5 and 6).

The motion was seconded by Kane and was subsequently passed by a vote of 5-0 (Hohlbauch absent).

 HPAC No. 2022-26: A request by Walter Deissler for a Conditional Use Permit to convert an existing single-family residence into a bed and breakfast inn and conduct exterior alterations to an existing guest house, within the R-1-5 (Single Family Residential, 5,000 square foot minimum site area) Zone. The project site is located at 513 North Encina Street (APN: 094-353-011).

Deissler recused himself since he is the consultant for the project. Davis also recused himself since he resides within 300 feet of the project site. This left three members to consider the item, one less than the four required for a quorum. As such, the item was continued to the meeting of January 11, 2023.

 HPAC No. 2022-27: A request by Walter Deissler for exterior alterations to a singlefamily residence and relocation of an accessory storage structure, within the R-1-5 (Single Family Residential, 5,000 square foot minimum site area) Zone. The project site is located at 301 West Race Avenue (APN: 094-353-003).

Deissler recused himself since he is the consultant for the project. Staff presented its report and recommended that HPAC approve the exterior alterations as conditioned by staff. Public comment in favor of the proposal was received from project consultant Walter Deissler. Deissler clarified that a new patio was not proposed, only additional paving. Davis asked whether an existing door near the staircase would remain. Deissler stated that it would be closed and altered into a window. Davis asked whether vertical siding on the building would remain. Deissler stated that it would be removed and replaced with horizontal siding similar to what exists on the structure already. Lastly Davis asked about the existing tree and whether it would be kept onsite. Deissler stated that he was unsure of the type and age of the tree, but that the owner wished to remove it. Davis asked staff if the HPAC could address the tree. Staff stated that they believed the Historic Preservation Ordinance allowed for the placement of conditions requiring the tree to be kept, but that it was an untested interpretation that could be challenged. Following discussion, a motion was made by Kane to approve the proposal as conditioned by staff, and to allow removal of the existing tree if necessary. The motion was seconded by Kreps. The motion passed by a vote of 4-0-1 (Hohlbauch absent, Deissler recused).

#### D. Discussion Items

- 1. Review of Committee Member Applications
  - a. Janelle Hickey
  - b. Karen Ayala

The HPAC conducted interviews of both candidates. Following discussion, a motion was made by Davis, seconded by Mulrooney, to nominate Karen Ayala to the Visalia City Council to fill the vacancy on the HPAC. Staff stated that the nomination would likely go before the City Council on January 16, 2023.

2. Goals Discussion

None.

- 3. Committee and Staff Comments
  - a. Project Updates

Staff provided updates on the following:

- Staff attempts to contact Community Relations Manager Allison Mackey to place the Architectural Style Guide on the City Newsletter;
- Obtaining clearances for HPAC members to volunteer at City offices;
- Finding of Consistency approval for Lee's Market, 540 N. Court Street;
- Solar panel installation issues at 506 W. Goshen Avenue;
- Unpermitted window changeout at 212 W. Race Avenue;
- Unpermitted exterior alterations at 311 W. Murray Avenue;
- Sidewalk repair at the intersection of Encina Street and Murray Avenue;
- Commission/Committee recognition event, March 2023.
- An Update on the tower at St. Mary's Catholic Church, 608 N. Church Street;
- Inclusion of Local Register update reclassifications into the City GIS system;
- Activation of Building Permit holds in the Accela permit system for historically designated sites.

Mulrooney asked if Deissler and/or staff could attend an upcoming information event being held by the Tulare County Associate of Realtors on February 16, 2023. Mulrooney stated that the Committee could provide information to the event attendees about historic preservation and designations in the City. Deissler also requested staff reach out to the Neighborhood Preservation Division regarding the proliferation of temporary carport structures in the Historic District.

4. Next HPAC Meeting: January 11, 2023

None.

5. Identification of Items for Future Agendas

None.

#### E. Adjournment

A motion was made by Kane, seconded by Davis, to adjourn the meeting. The motion passed 5-0 (Hohlbauch absent). The meeting adjourned at 7:06 p.m.

In compliance with the Americans Disabilities Act, if you need special assistance to participate in meetings call (559) 713-4443 (Staff Representative) 48-hours in advance of the meeting. For Hearing Impaired – Call (559) 713-4900 (TTY) 48-hours in advance of the scheduled meeting time to request signing services. Visually Impaired - If enlarged print or a Braille copy is desired, please request in advance of the meeting and services will be

provided as possible after the meeting. City Staff to the Committee is Cristobal Carrillo, Associate Planner, 559-713-4443, cristobal.carrillo@visalia.city.

Éste Aviso es para informarle que habra una audiencia para el público ante el Comité de Preservación Histórica de la Ciudad de Visalia. Para más información, o para dar comentario público respecto a esta solicitud, por favor llame Cristobal Carrillo, Associate Planner, al numero (559) 713-4443 o <u>cristobal.carrillo@visalia.city</u>.

Additional information about the Historic Preservation Advisory Committee may be found by contacting Cristobal Carrillo, Associate Planner at 559-713-4443, or emailing <u>cristobal.carrillo@visalia.city</u>.



# City of Visalia Memo



- **To:** Historic Preservation Advisory Committee
- From: Cristobal Carrillo, Associate Planner (559) 713-4443
- Date: January 11, 2023
- **Re:** Request for Public Hearing on January 11, 2023, for Historic Preservation Advisory Committee Item No. 2022-26 (Deissler).

#### **Recommended Action**

Staff recommends that the Historic Preservation Advisory Committee (HPAC) hold a continued public hearing on January 11, 2023, for consideration of HPAC Item No. 2022-26, take public comment, and approve the request as conditioned by staff.

#### Discussion

HPAC Item No. 2022-26 is a request by Walter Deissler for a Conditional Use Permit to convert an existing single-family residence into a bed and breakfast inn, and conduct exterior alterations to an existing guest house, within the R-1-5 (Single Family Residential, 5,000 square foot minimum site area) Zone. The project site is located at 513 North Encina Street (APN: 094-353-011). The item was continued at the December 14, 2023 meeting of the HPAC due to a lack of quorum to consider the proposal. Public hearing notices have been posted identifying the continued hearing date and revised meeting location. The comments for Site Plan Review No. 2022-182 have been included in the staff report. Otherwise, the analysis included in the December 14, 2022 staff report for HPAC Item No. 2022-26 remains unchanged. The December 14, 2022 staff report is attached to this memo.

#### Attachments:

• HPAC Item No. 2022-26 December 14, 2022 Staff Report



#### REPORT TO THE CITY OF VISALIA HISTORIC PRESERVATION ADVISORY COMMITTEE

**HEARING DATE**: December 14, 2022

PROJECT PLANNER: Cristobal Carrillo, Associate Planner Phone: (559) 713-4443 E-mail: <u>cristobal.carrillo@visalia.city</u>

SUBJECT: <u>Historic Preservation Advisory Committee Item No. 2022-26</u>: A request by Walter Deissler for a Conditional Use Permit to convert an existing residence into a bed and breakfast inn and conduct exterior alterations to an existing guest house, within the R-1-5 (Single Family Residential, 5,000 square foot minimum site area) Zone. The project site is located at 513 North Encina Street (APN: 094-353-011).

#### STAFF RECOMMENDATION

Staff recommends that the Historic Preservation Advisory Committee (HPAC) approve the proposed exterior alterations to the guest house and recommend approval of the Conditional Use Permit request to the Visalia Planning Commission.

#### SITE DATA

The site is zoned R-1-5 (Single Family Residential, 5,000 square foot minimum site area) and contains a single family residence, a detached guest house, and a storage building. The project site is located within



the Historic District and is listed on the Local Register of Historic Structures with an "Exceptional" classification. The structure contains "Victorian" and "Stick (Eastlake)" style architectural elements. Per the original City of Visalia Historic Survey, the structure was built in approximately 1888 and was originally owned by J.D. Hyde.

#### **PROJECT DESCRIPTION**

The applicant is requesting approval for the following items:

1. A request for a Conditional Use Permit (CUP) to convert an existing single-family residence into a bed and breakfast inn with up to four bedrooms for guests. Per the Operational Statement in Exhibit "D", the bed and breakfast inn would be solely operated and maintained by family of the property owners, who will also reside onsite. Breakfast

will either be provided onsite, or guests given vouchers for use at downtown Visalia establishments. Incidental retail sales will be conducted, consisting of the sale of books and inn related merchandise. Guests will be permitted to bring pets for their stay for an additional fee. Lastly, no exterior alterations are proposed to the main residence at this time.

2. Exterior interior alterations to an existing one bedroom/one bathroom guest house, to convert the structure into an Accessory Dwelling Unit with two bedrooms and two bathrooms. Per the elevations in Exhibit "C" this will include the addition of dormer windows to the east and west portions of the roof, to convert an existing unfinished second floor into livable space. Additional detail will also be added to the guest house to increase compatibility with the main residence, including wrought iron detail on the roof, and gridded wood gables on the dormer windows. All windows on the exterior walls of the guest house will be replaced with wood windows to match the main residence. French doors currently on the eastern end of the building will be removed in favor of new wood windows. Other features of the guest house, including circular balls on the eastern exterior siding and borders around the windows and doors, will be preserved.

Parking for the bed and breakfast will be provided via an existing paved area along the southern property boundary, providing five stalls. Existing landscaping shall remain. Hours of operation have not been provided. While signage is planned for the future, it will be submitted by the applicant for HPAC review at a later date. No other alterations to structures or features onsite are proposed at this time.

#### DISCUSSION


Zoning actions such as a CUP require a recommendation from the HPAC to the Visalia Planning Commission. Per the Historic Preservation Ordinance, the HPAC may recommend approval, conditional approval, modification, or disapproval of an application based upon the expected impact of the proposed zoning action on the historic or architectural significance of the affected structure, neighborhood, and/or the entire Historic District. Staff's recommendation to the HPAC is based on the considerations listed below.

#### Land Use Compatibility

The proposals meets the definition of a "Bed and breakfast inn" as it is a single family dwelling, predominantly residential in character, containing between three to six guestrooms, with overnight accomodation and a breakfast meal included in the lodging rate (a voucher program gualifies). Bed and breakfast inns are "conditionally permitted" for use in the R-1-5 Zone with

approval of а Conditional Use Permit, so long as property the is located within the Historic District or the Local on Register. Both are applicable for the project site.

The overall proposal is considered compatible with the



site and vicinity. The surrounding area consists primarily of architecturally significant residential uses, and the entire block is located within the Historic District. The proposed bed and breakfast use is not expected to produce noise or lighting impacts that would negatively affect adjacent areas, as the number of guest rooms is limited to four. Physical changes are limited solely to the guest house, which is not visible from the public right of way due to existing mature landscaping (see Figure 1). Physical changes proposed to the guest house would only increase compatibility of the accessory dwelling with the main residence through the inclusion of comparable windows, dormers, gables, and wrought iron roof features. Onsite parking provided would limit impacts to the surrounding streetscape, though given the size of the parcel, there is a significant amount of area available for off-site parking along the Encina Street property frontage.

#### Bed & Breakfast Regulations

Visalia Municipal Code (VMC) Section 17.32.150 (Bed and breakfast facilities) provides contains development criteria for the review of bed and breakfast inn proposals. Criteria provided ensures that inns are operated in a way that is compatible with surrounding residential areas. Based on the proposal submitted, the following considerations come into play:

 Parking: The VMC requires that the site meet the standards of the underlying zoning district, plus provide an additional parking stall per room available for lodging. The R-1-5 Zone requires two parking stalls for residential uses. Per the operational statement, four guest rooms will be provided, requiring an additional four parking stalls. As such, total parking demand for the use is six stalls. Per Exhibit "A" the applicant proposes five onsite parking stalls.

Parking is ultimately under the purview of the Visalia Planning Commission, which will be required to make a determination as part of their CUP review. VMC Section 17.56.090 (Exceptions to VMC requirements) permits the HPAC to make recommendations to the Planning Commission for exceptions to development standards such as parking. In this instance, staff recommends the HPAC recommend to the Planning Commission that the proposal be approved with five parking stalls, to limit potential impacts to the project site. The addition of a sixth parking stall could result in the loss of landscaping area and mature palm trees, negatively affecting the visual character of the project site.

- Owner Occupancy: The VMC requires that the owner of the bed and breakfast inn shall reside at the facility. Per the operational statement, the applicant states that "the property is owned by the Cain & Reyes Family Trust and will be occupied and run by the family." The applicant shall be required to verify compliance with the owner occupancy requirement prior to operation of the use.
- Scale and Appearance: The VMC requires that facilities remain primarily residential in character. No alterations are proposed to the main residence. Alterations proposed to the guest house will maintain the residential character and use of the structure.
- Signage: The VMC requires that signage for bed and breakfast inns be no taller than five feet in height, and no bigger than six square feet in size. No signage is proposed at this time. Once the applicant has arrived at a design for signage, the proposal will be brought before the HPAC for review and approval prior to issuance of a Building Permit for placement.

Compliance with all bed and breakfast inn development criteria is included as Condition of Approval No. 2.

#### Architectural Compatibility

Visalia Municipal Code Section 17.56.110 contains criteria for review of exterior alterations to structures listed on the Local Register. Criteria is aimed towards preserving original and distinguishing features of Local Register structures. No exterior alterations are proposed to the main residence, for which the Local Register designation mainly applies. As such, any distinguishing characters on the main residence will be preserved.

For the guest house, staff has determined that design criteria reserved for structures located within the Historic District is more appropriate (VMC Section 17.56.100), as it is unclear whether the guest house was original to the property. It is also unclear whether the accessory structure was originally intended as a garage or as a guest house. The guest house currently contains physical elements that are compatible with the main residence, specifically ball features on the eastern building exterior, and stylized bordering around all windows and entryways (see Figure 2). Per the applicant, these features will remain. The proposed addition of wood windows and a wrought iron roof feature will further increase compatibility with the main residence. Condition



of Approval No. 3 is included, requiring all new windows to match the existing main residence.

The addition of two dormer windows will significantly alter the appearance of the quest house. However, the shape of the dormers will be like those found on the main residence, with further compatibility

improved by placement of wood siding, wood windows, and gables. The dormers additions will not increase the overall height of the structure. No information has been provided detailing whether existing light fixtures on the guest house will be replaced. Condition of Approval No. 4 is included requiring any new light fixtures be compatible with the structures onsite as well as the Historic District. Given the above, the proposed alterations to the guest house will maintain compatibility with the site and surrounding areas. Also note, the view of the guest house will still be partially obstructed from view from the public right-of-way by existing landscaping.

#### **FINDINGS AND CONDITIONS**

For HPAC Item No. 2022-26 staff recommends that the Committee approve the proposed exterior alterations to the guest house, and recommend approval of the Conditional Use Permit request with five parking stalls as proposed by the applicant to the Visalia Planning Commission, based upon the following:

Findings:

- 1. The site is within the Historic District and is listed in the Local Register of Historic Structures.
- 2. That the proposal is in keeping with the purpose and intent of the Historic Preservation Element and Ordinance.

- 3. That the proposal will not be injurious to the surrounding properties or character of the Historic District due to its compatibility with the surrounding area.
- 4. That the Conditional Use Permit request for the bed & breakfast inn is consistent with the Zoning Ordinance, Historic Preservation Element, and Historic Preservation Ordinance.

Conditions:


- 1. That the project shall be developed in substantial compliance with the site plan in Exhibit "A", building elevations in Exhibits "B" and "C", and operational statement in Exhibit "D".
- 2. That the bed and breakfast inn shall be operated in compliance with all applicable development criteria listed in Visalia Municipal Code Section 17.32.150 (Bed and breakfast facilities).
- 3. That all new windows on the guest house shall have muntins similar in style to the main residence.
- 4. That any new light fixtures proposed for the Accessory Dwelling Unit be compatible with the structures onsite, and the Historic District.
- 5. That the proposal shall comply with all requirements of Site Plan Review No. 2022-182.
- 6. That the project undergoes the appropriate City permitting process.
- 7. That any significant changes in the operation of the proposed use, or any other changes to the exterior of onsite structures, be brought back to the Historic Preservation Advisory Committee prior to any review by the Planning Commission and/or issuance of a Building Permit.
- 8. That all other City codes and ordinances be met.

#### **Attachments**

- Exhibit "A" Site Plan
- Exhibit "B" Existing Building Elevations
- Exhibit "C" Guest House Proposed Elevations
- Exhibit "D" Operational Statements
- Aerial Map
- Historic District and Local Register Map

#### APPEAL INFORMATION

According to the City of Visalia Zoning Ordinance Section 17.56.060, an appeal to the City Council may be submitted within ten days following the date of a decision by the Historic Preservation Advisory Committee (HPAC). An appeal shall be in writing and shall be filed with the City Clerk at 220 N. Santa Fe Street. The appeal shall specify errors or abuses of discretion by the HPAC, or decisions not supported by the evidence in the record. The appeal form can be found on the city's website www.visalia.city or from the City Clerk.



# SCOPE OF WORK

513 N Encina currently has a main residence with a guest house. The **current guest house/ADU** will be expanded from a 1 BR /1 Bath to a 2 BR/ 2 Bath. The currently an unfinished second floor with stair access. 1 BR and 1 Bath will be added to the second floor. To accommodate this, we shall add dormers on th east and west sides, as shown in the attached elevations. Additionally, we shamatch the gable end detail from the main house. The roof will have the wroug iron detail that matches the main house. We shall also replace the french do on the east elevation with 2 windows matching the main house. The north si aluminum sliding window will be replaced with a fixed window and the 2 window the west side will be replaced with 2 wood windows.

Site work will consist of no changes. Currently there are 5 parking spaces will remain along with existing fencing and other paving.

**Roof** will be redwood or cedar shingle. See attached fireproofing specs. T keep the building consistent with the original main house roof.

Siding and other wood details will match existing.











	WALTER DEISSLER ARCHITECT ARCHITECT 2 I 35 E HARVARD CPURT VISALIA, CA 93292 PHONE " 559-901-0500 EMAIL : WDEIS I @HOTMAIL.COM	PROPOSED ADU AND BED \$BREAKFAST TC ANICINA ST, VISALIA, CA.	STAMP : NOIDATE DESCRIPTION	DRAWN BY : DWG DATE :	REVIEWED BY : PROJECT NUMBER : SHEET : SHEET TITLE :	A B B
×						




0.1

**ROPOSED** 

NORT



OPOSED




POSED






WEST



# EXISTING



# EXISTING



EXISTING

#### The JD Hyde House

Historic Inn 513 N Encina Street, Visalia, California

#### Bed & Breakfast Operations Statement

This amazingly intact historic house is currently being added to the National Register of Historic Places and will be perfectly restored and furnished to its authentic Eastlake Victorian grandeur. Rather than only using the home for ourselves, we plan to share 3 or 4 bedrooms of our house with guests and visitors. The property is owned by the Cain & Reyes Family Trust and will be occupied and run by the family.

There are currently 5 parking spaces on the property, 4 of which can be used by guests. A light, continental breakfast will be served daily, although we may explore a breakfast voucher program with local restaurants- perhaps the 210 coffee shop or the Darling hotel. The plan would be to get our guests walking downtown and spending money at other venues and businesses.

We may also have a small display case in one of the public rooms of the property to sell our own themed Christmas ornament, sweatshirt, or Visalia history books, etc. We may wish to have a small sign made to hang from the lamp post on the property out front; if we decide we'd like this, we will send the design and sign to the planning dept for approval.

Our four rooms would have a max occupancy of 1 (the back suite) or 2 guests (the front suites), so our maximum number of guests on any given night would be 7. We would also allow small pets for a fee. Rooms would be available to book through our own website and all major hospitality platforms (Expedia, Booking.com, AirBNB, etc).

We (the family) would take care of all aspects of the business, from cleaning toilets to acting as a guest concierge. There would not be any additional employees needed for this size of B&B. The family members (ourselves) would occupy the ADU and one of the suites inside the main house.

If you have any questions regarding our operations, please feel free to contact me via email at jcain310@gmail.com

Joshua Cain, André Reyes, Dezirae Reyes The Cain Reyes Family Trust

#### **SCOPE OF WORK**

513 N Encina currently has a main residence with a guest house. The **current guest house/ADU** will be expanded from a 1 BR /1 Bath to a 2 BR/ 2 Bath. There is currently an unfinished second floor with stair access. 1 BR and 1 Bath will be added to the second floor. To accommodate this, we shall add dormers on the east and west sides, as shown in the attached elevations. Additionally, we shall match the gable end detail from the main house. The roof will have the wrought iron detail that matches the main house. We shall also replace the french doors on the east elevation with 2 windows matching the main house. The north side aluminum sliding window will be replaced with a fixed window and the 2 windows on the west side will be replaced with 2 wood windows.

**Site work** will consist of no changes. Currently there are 5 parking spaces which will remain along with existing fencing and other paving.

**Roof** will be redwood or cedar shingle. See attached fireproofing specs. This will keep the building consistent with the original main house roof.

Siding and other wood details will match existing.

City of Visalia

315 E. Acequia Ave., Visalia, CA 93291



Site Plan Review

December 12, 2022

#### Site Plan Review No. 2022-182

Pursuant to Zoning Ordinance Chapter 17.28 the Site Plan Review process has found that your application complies with the general plan, municipal code, policies, and improvement standards of the city. A copy of each Departments/Divisions comments that were discussed with you at the Site Plan Review meeting are attached to this document.

Based upon Zoning Ordinance Section 17.28.070, this is your Site Plan Review determination. However, your project requires discretionary action as stated on the attached Site Plan Review comments. You may now proceed with filing discretionary applications to the Planning Division.

This is your Site Plan Review Permit; your Site Plan Review became effective **November 23, 2022.** A site plan review permit shall lapse and become null and void one year following the date of approval unless, prior to the expiration of one year, a building permit is issued by the building official, and construction is commenced and diligently pursued toward completion.

If you have any questions regarding this action, please call the Community Development Department at (559) 713-4359.

Respectfully,

Paul Bernal Community Development Director 315 E. Acequia Ave. Visalia, CA 93291

Attachment(s):

Site Plan Review Comments

City of Visalia

315 E. Acequia Ave., Visalia, CA 93291



**Planning Division** 

Tel: (559) 713-4359; Fax: (559) 713-4814

Fire Dept.

MEETING DATE SITE PLAN NO. PARCEL MAP NO. SUBDIVISION LOT LINE ADJUSTMENT NO.

November 23, 2022 2022-182

Enclosed for your review are the comments and decisions of the Site Plan Review committee. Please review all comments since they may impact your project.

**RESUBMIT** Major changes to your plans are required. Prior to accepting construction drawings for building permit, your project must return to the Site Plan Review Committee for review of the revised plans.

During site plan design/policy concerns were identified, schedule a meeting with

Planning Engineering prior to resubmittal plans for Site Plan Review.

Solid Waste Parks and Recreation

### $\boxtimes$

**REVISE AND PROCEED** (see below)

- A revised plan addressing the Committee comments and revisions must be submitted for Off-Agenda Review and approval prior to submitting for building permits or discretionary actions.
- Submit plans for a building permit between the hours of 9:00 a.m. and 4:00 p.m., Monday through Friday.

$\boxtimes$	Your plans must be reviewed by:	
		REDEVELOPMENT
	PLANNING COMMISSION	PARK/RECREATION
		OTHER – Lot Line Adjustment
	ADDITIONAL COMMENTS:	

If you have any questions or comments, please call the Site Plan Review Hotline at (559) 713-4440 Site Plan Review Committee

# SITE PLAN REVIEW COMMENTS

#### Josh Dan, Planning Division (559) 713-4003

Date: November 23, 2022

SITE PLAN NO:	2022-182
PROJECT:	The Hyde Historic Inn
DESCRIPTION:	REMODEL AND COMPLETE GUEST HOUSE (ADU) AND USE MAIN HOUSE
	AS A 4 ROOM BED AND BREAKFAST (R-1-5)
APPLICANT:	WALTER DEISLER
PROP. OWNER:	LEE JACKY W (TR)
LOCATION:	513 N. ENCINA ST.
APN TITLE:	094-353-011
GENERAL PLAN:	RLD (Residential Low Density)
ZONING:	R-1-5 (Single Family Residential, 5,000 sq. ft. minimum site area)

#### Planning Division Recommendation:

- Revise and Proceed
- Resubmit

#### Project Requirements

- HPAC Review
- Conditional Use Permit (CUP)
- Additional Information as Needed

#### PROJECT SPECIFIC INFORMATION: September 28, 2022

- 1. The proposal to establish a Bed and Breakfast will the require the applicant to comply with Section 17.32.150 Bed and breakfast facilities of the VMC.
- 2. Located within the Historic District and requires Historic Preservation Advisory Committee review.
- 3. The applicant shall provide an operational statement detailing the uses in the proposed buildings.
- a. The operational statement shall provide a clearer description of compliance with owner occupancy requirement of the B&B requirements of the code.
- 4. Staff are requesting the applicant provide floor plans of the buildings and proposed remodel.
- 5. Parking shall comply with VMC 17.32.150.D.2 i.e.: one space per room available for lodging.
- 6. Meet all other Codes and Ordinances.

#### Notes:


- 1. The applicant shall contact the San Joaquin Valley Air Pollution Control District to verify whether additional permits are required to conduct the proposed use.
- 2. Prior to completion of a final building inspection for a project, a signed <u>MWELO Certificate</u> of <u>Compliance</u> shall be submitted indicating that all landscaping has been installed to MWELO standards.

#### Applicable sections of the Visalia Municipal Code, Title 17 (Zoning):

- 17.12 Single-Family Residential Zone
- 17.30 Development Standards
- 17.32.150 Bed and breakfast facilities
- 17.34 Off-street parking and loading facilities
- **17.56 Historic Preservation District**

NOTE: <u>Staff recommendations contained in this document are not to be considered support for</u> <u>a particular action or project unless otherwise stated in the comments. The comments found on</u> <u>this document pertain to the site plan submitted for review on the above referenced date. Any</u> <u>changes made to the plan submitted must be submitted for additional review.</u>

Signature:



# BUILDING/DEVELOPMENT PLAN REQUIREMENTS **ENGINEERING DIVISION**

Adrian Rubalcaba	713-4271
Ather Razaq	713-4268
Edelma Gonzalez	713-4364
Jaklin Rowley	713-4369
Luqman Ragabi	713-4362
Lupe Garcia	713-4197

#### ITEM NO: 2 DATE: NOVEMBER 23, 2022

SITE PLAN NO.: PROJECT TITLE: DESCRIPTION:	22-182 THE HYDE HISTORIC INN REMODEL AND COMPLETE GUESS HOUSE
	(ADU) AND USE MAIN HOUSE AS A 4 ROOM BED AND BREAKFAST. (R-1-5)
APPLICANT:	WALTER DEISLER
PROP OWNER: LOCATION:	LEE JACKY W (TR) 513 N . ENCINA ST
APN:	094-453-011

#### DI ANI DEVI

SITE PLAN REVIEW COMMENTS
REQUIREMENTS (indicated by checked boxes)
Install curb return with ramp, with radius;
Install curb; I gutter
Drive approach size: Use radius return;
Sidewalk: width; parkway width at
Repair and/or replace any sidewalk across the public street frontage(s) of the subject site that has become uneven, cracked or damaged and may constitute a tripping hazard.
Replace any curb and gutter across the public street frontage(s) of the subject site that has become uneven and has created areas where water can stand.
Right-of-way dedication required. A title report is required for verification of ownership. 2' DEDICATION FOR ALLEY WAY IF PROJECT DEEMED TO BE A CHANGE ON USE
Deed required prior to issuing building permit;
City Encroachment Permit Required. FOR ALL WORK NECESSARY WITHIN PUBLIC RIGHT-OF-WAY Insurance certificate with general & auto liability (\$1 million each) and workers compensation (\$1 million), valid business license, and appropriate contractor's license must be on file with the City, and valid Underground Service Alert # provided prior to issuing the permit. Contact Encroachment Tech. at 713-4414.
CalTrans Encroachment Permit required. CalTrans comments required prior to issuing building permit. Contacts: David Deel (Planning) 488-4088;
Landscape & Lighting District/Home Owners Association required prior to approval of Final Map. Landscape & Lighting District will maintain common area landscaping, street lights, street trees and local streets as applicable. Submit completed Landscape and Lighting District application and filing fee a min. of 75 days before approval of Final Map.
Landscape & irrigation improvement plans to be submitted for each phase. Landscape plans will need to comply with the City's street tree ordinance. The locations of street trees near intersections will need to comply with Plate SD-1 of the City improvement standards. A street tree and landscape master plan for all phases of the subdivision will need to be submitted with the initial phase to assist City staff in the formation of the landscape and lighting assessment district.
□ Grading & Drainage plan required. If the project is phased, then a master plan is required for the entire project area that shall include pipe network sizing and grades and street grades. □ Prepared by registered civil engineer or project architect. □ All elevations shall be based on the City's benchmark network. Storm run-off from the project shall be handled as follows: a) □ directed to the City's existing storm drainage system; b) □ directed to a permanent on-site basin; or c) □ directed to a temporary on-site basin is required until a connection with adequate capacity is available to the City's storm drainage system. On-site basin: □ maximum side slopes, perimeter fencing required, provide access ramp to bottom for maintenance.
Grading permit is required for clearing and earthwork performed prior to issuance of the building permit. Show finish elevations. (Minimum slopes: A.C. pavement = 1%, Concrete pavement = 0.25%. Curb & Gutter = .020%, V-gutter = 0.25%)
Show adjacent property grade elevations. A retaining wall will be required for grade differences greater than 0.5 feet at the property line.
All public streets within the project limits and across the project frontage shall be improved to their full width, subject to available right of way, in accordance with City policies, standards and specifications.

Traffic indexes per city standards: Install street striping as required by the City Engineer. Install landscape curbing (typical at parking lot planters). Minimum paving section for parking: 2" asphalt concrete paving over 4" Class 2 Agg. Base, or 4" concrete pavement over 2" sand. Design Paving section to traffic index of 5.0 min. for solid waste truck travel path. Provide "R" value tests: each at Written comments required from ditch company Contacts: James Silva 747-1177 for Modoc, Persian, Watson, Oakes, Flemming, Evans Ditch and Peoples Ditch; Jerry Hill 686-3425 for Tulare Irrigation Canal, Packwood and Cameron Creeks; Bruce George 747-5601 for Mill Creek and St. John's River. Access required on ditch bank. 15' minimum Provide wide riparian dedication from top of bank. Show Valley Oak trees with drip lines and adjacent grade elevations. Derotect Valley Oak trees during construction in accordance with City requirements. A permit is required to remove Valley Oak trees. Contact Public Works Admin at 713-4428 for a Valley Oak tree evaluation or permit to remove. A pre-construction conference is required. Relocate existing utility poles and/or facilities. Underground all existing overhead utilities within the project limits. Existing overhead electrical lines over 50kV shall be exempt from undergrounding. Subject to existing Reimbursement Agreement to reimburse prior developer: Fugitive dust will be controlled in accordance with the applicable rules of San Joaquin Valley Air District's Regulation VIII. Copies of any required permits will be provided to the City. If the project requires discretionary approval from the City, it may be subject to the San Joaquin Valley Air District's Rule 9510 Indirect Source Review per the rule's applicability criteria. A copy of the approved AIA application will be provided to the City.

If the project meets the one acre of disturbance criteria of the State's Storm Water Program, then coverage under General Permit Order 2009-0009-DWQ is required and a Storm Water Pollution Prevention Plan (SWPPP) is needed. A copy of the approved permit and the SWPPP will be provided to the City.

Comply with prior comments. Resubmit with additional information. Redesign required.

#### Additional Comments:

- 1. Proposed project will incur impact fees based on number of rooms if deemed to be a change in use. Refer to page 3 for applicable fees due at time of building permit issuance.
- 2. A building permit is required, standard plan check and inspection fees will apply.
- 3. Additional 2-foot of right-of-way along the alleyway is required if deemed to be change in use. Grant Deed submittal to follow City procedure, refer to City website for document formatting and submittal. Further coordinate with City Engineer.
- 4. Project will be required to repair any dilapidated/shifted/uneven sidewalks or curbs and gutters.
- 5. If there is a change in use, onsite improvements would be required. Typical improvements to include accessible parking and accessible path of travel to public right-of-way.
- 6. Project in Flood Zone AE, comply with FEMA requirements.

#### SUMMARY OF APPLICABLE DEVELOPMENT IMPACT FEES

#### Site Plan No: 22-182 11/23/2022 Date:

Summary of applicable Development Impact Fees to be collected at the time of building permit:

(Preliminary estimate only! Final fees will be based on the development fee schedule in effect at the time of building permit issuance.)

(Fee Schedule Date: 08/20/2022) (Project type for fee rates: BED AND BREAKFAST PLUS ADU UNIT)

Existing uses may qualify for credits on Development Impact Fees. **1-SFD** 

FEE ITEM	FEE RATE
Groundwater Overdraft Mitigation Fe	e
Transportation Impact Fee	\$3,105/ROOM
	CREDIT SFD: \$7,097/UNIT
Trunk Line Capacity Fee	\$89/ROOM
	TREATMENT: \$508/ROOM
Sewer Front Foot Fee	
Storm Drain Acq/Dev Fee	
Park Acq/Dev Fee	
Northeast Specific Plan Fees	
Waterways Acquisition Fee	
Public Safety Impact Fee: Police	
Public Safety Impact Fee: Fire	
Public Facility Impact Fee	\$140/ROOM
Parking In-Lieu	

#### **Reimbursement:**

- 1.) No reimbursement shall be made except as provided in a written reimbursement agreement between the City and the developer entered into prior to commencement of construction of the subject facilities.
- 2.) Reimbursement is available for the development of arterial/collector streets as shown in the City's Circulation Element and funded in the City's transportation impact fee program. The developer will be reimbursed for construction costs and right of way dedications as outlined in Municipal Code Section 16.44. Reimbursement unit costs will be subject to those unit costs utilized as the basis for the transportation impact fee.
- 3.) Reimbursement is available for the construction of storm drain trunk lines and sanitary sewer trunk lines shown in the City's Storm Water Master Plan and Sanitary Sewer System Master Plan. The developer will be reimbursed for construction costs associated with the installation of these trunk lines.

Edelma Gonzalez

#### <u>City of Visalia</u> Building: Site Plan Review Comments

# THE HYDE HEJORIC INN 513 NENCINA ST.

NOTE: These are general comments and DO NOT constitute a complete plan check for your specific project Please refer to the applicable California Code & local ordinance for additional requirements.

	A building permit will be required. FOR ALL IMPROVEMENTS For information call (559) 713-4444	
$\bowtie$	Submit 1 digital set of professionally prepared plans and 1 set of calculations. (Small Tenant Improvements)	
	Submit 1 digital set of plans prepared by an architect or engineer. Must comply with 2016 California Building Cod Sec. 2308 for conventi light-frame construction or submit 1 digital set of engineered calculations.	onal
	Indicate abandoned wells, septic systems and excavations on construction plans.	
	You are responsible to ensure compliance with the following checked items: Meet State and Federal requirements for accessibility for persons with disabilities.	
(	A path of travel, parking and common area must comply with requirements for access for persons with disabilities.	
	All accessible units required to be adaptable for persons with disabilities.	
	Maintain sound transmission control between units minimum of 50 STC.	
	Maintain fire-resistive requirements at property lines.	
X	A demolition permit & deposit is required. FOR SNY DEMO WORK For information call (559) 713-4444	
$\mathbf{X}$	Obtain required permits from San Joaquin Valley Air Pollution Board. For information call (661) 392-5500	
	Plans must be approved by the Tulare County Health Department. For information call (559) 624-8011	
$\boxtimes$	Project is located in flood zone <u>LE</u> Hazardous materials report. <u>MEET FEMA FLOOD</u> REQUIREMENT	
	Arrange for an on-site inspection.       (Fee for inspection \$157.00)       For information call (559) 713-4444	1917
	School Development fees.	
	Park Development fee \$ per unit collected with building permits.	
	Additional address may be required for each structure located on the site, For Information call (559) 713-4320	
	Acceptable as submitted	
	No comments at this time	
	Additional comments:	

ALCIA 11/20/22 A Signature

FIRE STL CERTING WITH FULLY LOSS	Site Plan Comments Visalia Fire Department Corbin Reed, Fire Marshal 420 N. Burke Visalia CA 93292 559-713-4272 office prevention.division@visalia.city	Date Item # Site Plan # APN:	November 22, 2022 2 22182 094353011
-------------------------------------	---	---------------------------------------	--

- The Site Plan Review comments are issued as general overview of your project. With further details, additional requirements will be enforced at the Plan Review stage. Please refer to the 2019 California Fire Code (CFC), 2019 California Building Codes (CBC) and City of Visalia Municipal Codes.
- Address numbers must be placed on the exterior of the building in such a position as to be clearly and plainly
  visible from the street. Numbers will be at least four inches (4") high and shall be of a color to contrast with
  their background. If multiple addresses are served by a common driveway, the range of numbers shall be posted
  at the roadway/driveway. 2019 CFC 505.1
- All hardware on exit doors, illuminated exit signs and emergency lighting shall comply with the 2019 California Fire Code. This includes all locks, latches, bolt locks, panic hardware, fire exit hardware and gates.
- Commercial dumpsters with 1.5 cubic yards or more shall not be stored or placed within 5 feet of combustible walls, openings, or a combustible roof eave line except when protected by a fire sprinkler system. 2019 CFC 304.3.3
- A Knox Box key lock system is required. Where access to or within a structure or area is restricted because of secured openings (doors and/or gates), a key box is to be installed in an approved location. Go to knoxbox.com to order and please allow adequate time for shipping and installation. 2019 CFC 506.1
- Commercial cooking appliances and domestic cooking appliances used for commercial purposes that produce grease laden vapors shall be provided with a Type 1 Hood, in accordance with the California Mechanical Code, and an automatic fire extinguishing system. 2019 CFC 904.12 & 609.2
- **Special comments**: This proposal will designate the property as a Lodging House which is not considered a change in use at this time. Applicable code requirements for a Lodging House shall be implemented within the home and will be inspected on an annual basis.

Corbin Reed Fire Marshal



City of Visalia Police Department 303 S. Johnson St. Visalia, CA 93292 (559) 713-4370

Date:	11/2	2/2022	
Item:	2		
Site P	lan:	SPR22182	
Name	· Vir	ncent Muto	

#### Site Plan Review Comments

No Comment at this time.
Request opportunity to comment or make recommendations as to safety issues as plans are developed.
Public Safety Impact Fee: Ordinance No. 2001-11 Chapter 16.48 of Title 16 of the Visalia Municipal Code Effective date - August 17, 2001.
Impact fees shall be imposed by the City pursuant to this Ordinance as a condition of or in conjunction with the approval of a development project. "New Development or Development Project" means any new building, structure or improvement of any parcels of land, upon which no like building, structure of improvement previously existed. *Refer to Engineering Site Plan comments for fee estimation.
Not enough information provided. Please provide additional information pertaining to:
Territorial Reinforcement: Define property lines (private/public space).
Access Controlled/ Restricted etc.
lighting Concerns: ample lighting to deter criminal activity
Traffic Concerns:
Surveillance Issues: Exterior surveillance cameras to deter/capture criminal activity
Line of Sight Issues: Low shrubbery to deter transient activity
Other Concerns:

## SITE PLAN REVIEW COMMENTS

#### **CITY OF VISALIA TRAFFIC SAFETY DIVISION**

#### November 23, 2022

ITEM NO: 2 SITE PLAN NO: SPR22182 PROJECT TITLE: The Hyde Historic Inn DESCRIPTION: Remodel and Complete Guest House (ADU)and Use Main House as a 4 Room Bed & Breakfast. (R-1-5 APPLICANT: Walter Deisler OWNER: LEE JACKY W (TR) APN: 094353011 LOCATION: 513 N ENCINA ST

#### THE TRAFFIC DIVISION WILL PROHIBIT ON-STREET PARKING AS DEEMED NECESSARY

No Comments

- See Previous Site Plan Comments
- Install Street Light(s) per City Standards at time of development.
- □ Install Street Name Blades at Locations at time of development.
- □ Install Stop Signs at *local road intersection with collector/arterial* Locations.
- Construct parking per City Standards PK-1 through PK-4 at time of development.
- Construct drive approach per City Standards at time of development.
- Traffic Impact Analysis required (CUP)
  - Provide more traffic information such as
     Depending on development size, characteristics, etc., a
     TIA may be required.
- Additional traffic information required (Non Discretionary)
  - Trip Generation Provide documentation as to concurrence with General Plan.
  - Site Specific Evaluate access points and provide documentation of conformance with COV standards. If noncomplying, provide explanation.
  - Traffic Impact Fee (TIF) Program Identify improvments needed in concurrence with TIF.

#### **Additional Comments:**

Leslie Blair

Leslie Blair

22-182

SOLID WASTE DIVISION 336 N. BEN MADDOX VISALIA CA. 93291 713 - 4532 COMMERCIAL BIN SERVICE		22182			
XX	No comments.	November 23, 2022			
	See comments below				
	Revisions required prior to subm	itting final plans. See comments I	below.		
	Resubmittal required. See comm	ents below.			
	Customer responsible for all cardboard and other bulky recyclables to be broken down before disposing of in recycle containers				
	ALL refuse enclosures must be l	R-3 OR R-4			
	Customer must provide combina	tion or keys for access to locked	_ gates/bins		
XX	Type of refuse service not indica	ted.			
	Location of bin enclosure not ac	ceptable. See comments below.			
	Bin enclosure not to city standar	ds double.			
	Inadequate number of bins to pro	ovide sufficient service. See comn	nents below.		
	Drive approach too narrow for re	fuse trucks access. See comment	ts below.		
	Area not adequate for allowing refuse truck turning radius of : Commercial 50 ft. outside 36 ft. inside; Residential 35 ft. outside, 20 ft. inside.				
	Paved areas should be engineer	ed to withstand a 55,000 lb. refuse	truck.		
	Bin enclosure gates are required				
	Hammerhead turnaround must b	e built per city standards.			
	Cul - de - sac must be built per c	ity standards.	_		
	Bin enclosures are for city refuse stored inside bin enclosures.	e containers only. Grease drums o	or any other items are n	ot allowed to be	
	Area in front of refuse enclosure	must be marked off indicating no	parking		
	Enclosure will have to be design clear space in front of the bin, in	ed and located for a STAB service cluded the front concrete pad.	e (DIRECT ACCESS) wit	h no less than 38'	
	Customer will be required to roll	container out to curb for service.			
	Must be a concrete slab in front of enclosure as per city standards, the width of the enclosure by ten(10 feet, minimum of six(6) inches in depth.				
		clearance of 3 feet from any wall front of the compactor to allow the			
	City ordinance 8.28.120-130 (effe construction debris unless trans franchise permittee for removal o	ctive 07/19/18) requires contractor ported in equipment owned by co of debris utilizing roll-off boxes.	r to contract with City f ntractor or unless cont	or removal of racting with a	
Comment	Customer confirmed this project will not require any changes to the exisiting residential services assigned.				
	Jason Serpa, Solid Waste Manager, 559-713-4533 Edward Zuniga, Solid Waste Supervisor, 559-713-4338 Mathan Garza, Solid Waste,559-713-4338				

City of Visalia

7579 Ave. 288, Visalia, CA 93277



**Public Works** 

(559) 713-4465 Jax (559) 713-4501

SITE PLAN REVIEW DATE: \_\_\_\_\_

#### WASTEWATER COLLECTIONS AND PRETREATMENT DIVISION (QUALITY ASSURANCE) SITE PLAN REVIEW COMMENTS

SITE PLAN REVIEW NO: \_\_\_\_\_

THE HYDE HISTORIC INN PROJECT NAME:

THE PROJECT IS SUBJECT TO THE FOLLOWING REQUIREMENTS FROM WASTEWATER PRETREATMENT DIVISION (QUALITY ASSURANCE):

> SUBMISSION OF WASTEWATER DISCHARGE PERMIT APPLICATION/QUESTIONAIRRE/OTHER REGULATORY FORMS

- FOOD SERVICE EST QUEST
- FORM REQUIRED
- FORM REQUIRED

**INSTALLATION OF SAND AND GREASE INTERCEPTOR** 

■ INSTALLATION GREASE INTERCEPTOR

GREASE TRAP

SITE PLAN REVIEWED-NO COMMENTS

CONTACT THE WASTEWATER PRETREATMENT DIVISION (QUALITY ASSURANCE) AT (559) 713-4529 OR JESSICA.SANDOVAL@VISALIA.CITY, IF YOU HAVE ANY QUESTIONS.

COMMENTS:

FORMS CAN BE FOUND @


https://www.visalia.city/depts/public works/wastewater/commercial industrial pretreatment\_prog ram.asp

DATE REVIEWED: 11/22/22

## **Aerial Map**



# Historic District and Local Register Map



# City of Visalia Memo

NISALIA
Founded 1852

To:	Historic Preservation Advisory Committee	
From:	Cristobal Carrillo, Associate Planner	Found
Date:	January 11, 2023	
Re:	Historic Preservation Advisory Committee Cal	endar for 2023

The following dates are set for Historic Preservation Advisory Committee regular meetings in 2023. Note that this list does not preclude the scheduling of Special Called meetings by the HPAC if necessary.

- 1. January 11, 2023
- 2. January 25, 2023
- 3. February 8, 2023
- 4. February 22, 2023
- 5. March 8, 2023
- 6. March 22, 2023
- 7. April 12, 2023
- 8. April 26, 2023
- 9. May 10, 2023
- 10. May 24, 2023
- 11. June 14, 2023
- 12. June 28, 2023
- 13. July 12, 2023
- 14. July 26, 2023
- 15. August 9, 2023
- 16. August 23, 2023
- 17. September 13, 2023
- 18. September 27, 2023
- 19. October 11, 2023
- 20. October 25, 2023
- 21. November 8, 2023
- 22. November 22, 2023 No Meeting
- 23. December 13, 2023
- 24. December 27, 2023 No Meeting